COMMONWEALTH OF VIRGINIA

COUNTY OF HENRICO

CECELIA H. STOWE, CPPO, C.P.M.
PURCHASING DIRECTOR
DEPARTMENT OF FINANCE

FOR THE COMPLETE ADDENDUM GO TO www.ebidexchange.com/henrico

ADDENDUM NO. 1

TO:	Prospective Bidders and Others Concerned
FROM:	County of Henrico/Draper Aden Associates
DATE:	November 26, 2014
RE:	ITB # 14-9663-10CE
	Hermitage Court and Bryan Park Heights Area (SH-02A) Sanitary Sewer Rehabilitation

The following changes, corrections, deletions, clarifications, and/or additions constitute Addendum No. 1. Please acknowledge receipt of this Addendum No. 1, dated November 26, 2014 on the Bid Form when returning your Bid package. **Failure to acknowledge this addendum may result in your bid being declared non-responsive.** All other general terms, conditions and specifications shall remain the same.

Corrections:

Plan Sheet 8: The pipe bursting insertion pit shall be 20' long by 6' wide.

Plan Sheet 33: At 2210 Nelson Street, the Contractor shall install a new 1" corporation stop, 1" service from the main to the meter, copper setter for a 5/8" meter, and meter box. Contractor shall connect the new water service to the existing service on the private side of the new meter and abandon the existing water service from the main to the meter.

Project Manual, Section 00010: **REMOVE** Section 00010 and **REPLACE** with the attached Section 00010, "Table of Contents."

Additions:

Project Manual, Section 02723: **ADD** the attached Section 02723, **"**Pipe Bursting Method Sewer Replacement."

Bidder Inquiries and Responses:

Question: Are maximum bypass pumping flows provided?
Response: No – design of the bypass system shall be in accordance with Project Manual Section 02420.

Question: No rehab instructions are provided for the following manholes: #29, #49, #54, #56, #67, #73, and #79. What is the intent for these manholes?
Response: These are precast manholes in good condition. No rehabilitation is required.

Question: On Plan Sheet 5, what is required for relocation of the cat remains?
Response: Contractor shall remove the cat remains by scooping a bucket of dirt from the area, as noted on the plans. Contractor shall coordinate with the property owner to bury the remains in a location outside of the County easement. All coordination with the property owner shall be done after award of the project.