

**HENRICO COUNTY DEPARTMENT OF PUBLIC UTILITIES  
UPHAM BROOK TRUNK SEWER**

**Public Information Meeting**

August 8, 2018

**Purpose of the Project:**

- The purpose of this project is to reduce the occurrence of sanitary sewer overflows and provide additional capacity for growth in demands. The proposed sewer will be located generally parallel to existing concrete 48-inch and 54-inch diameter sewer mains, installed in the early 1980's, from Staples Mill Road near Dickens Road to just east of Brook Road at Upham Brook.

**Scope of Work:**

- Install approximately 14,200 linear feet of 48-inch sanitary sewer main piping.
- Install approximately 1,500 linear feet of 54-inch sanitary sewer main piping.
- Rehabilitate approximately 2,450 linear feet of 8-inch diameter sanitary sewer piping.
- Five (5) 72-inch diameter tunnels, beneath Brook Road (Route 1), Dumbarton Avenue, Lakeside Avenue, and Byrdhill Road and a CSX railroad crossing.
- Two (2) cast-in-place diversion structures.
- Where "open cutting" is performed, repave the area of the streets and reseed and restore easement areas upon completion of the utility work.

**Construction Topics:**

- The construction contractor, Garney Companies, Inc., will start work the week of August 13, 2018 and will complete the work by February 2021, weather permitting.
- Normal working hours will be 7 a.m. to 6 p.m., Monday thru Saturday. Work hours within the County road right-of-way in residential areas will be limited to 9:00 a.m. through 5:00 p.m., Monday through Friday. Typically, work will not occur on Sunday or County Holidays.
- There will be 3 road closures. All lanes must be re-opened to traffic at the end of each workday.

Buckingham Avenue: Street shall be closed during construction and a detour in effect (Lakeside Avenue - Wedgewood Avenue/Winwood Road – Buckingham Avenue – Bryan Park Avenue).

Bryan Park Avenue: Four phases of construction along Bryan Park Avenue are planned and are to be detoured for each. Detours will be in place 24 hours a day during the applicable phase. Length of work zone shall be limited to 200 feet at any time. Access to Bryan Park Avenue shall be via detour from Lakeside Avenue while work is ongoing along Bryan Park Avenue (Lakeside Avenue - Wedgewood Avenue/Winwood Road – Buckingham Avenue – Wedgewood Avenue – Westlake Avenue/Mowbray Avenue/Stoneleigh Road - Bryan Park Avenue).

Hill Drive: At least 1 traffic lane, 11ft wide minimum, shall be maintained at all times utilizing flaggers.

- Access to homes will be maintained for residents. When traveling in the area, everyone is urged to drive with caution while crews complete the work.

**Henrico County Contacts For This Project:**

Melvin Slough	Community Liaison	501-7540
Todd Trimmer	Inspector	241-6570
Jason Garofalo	Project Engineer	727-8728
Lee Maddox	Construction Division Director	727-8730